



# General Overview of JADA procurement activities

T. Inoue for Y. Kusama

ITER Japan

National Institutes

for Quantum and Radiological Science and Technology



IBF/17

29<sup>th</sup> March, 2017

Palais des Papes, Avignon

- **Introduction:** Road map to fusion energy
- **In-kind Procurement by Japan**
  - ITER components to be procured by Japan
  - Procurement Arrangement status
  - Procurement progress
- **Expected contracts**
  - Procurement to be launched
  - On-site activities
  - Support by European companies
- **Summary**



# QST Roadmap to Fusion Energy



3<sup>rd</sup> phase of the fusion R&D plan by the Atomic Energy Commission, June 1992

**Plasma Experiment Phase**


Scientific feasibility

**Experimental Reactor Phase**

Scientific/Technical Feasibility

**ITER**

- 500 MW Fusion power
- Continuous fusion burning



**Prototype Reactor Phase**

Technical demonstration  
Economical Feasibility

**Prototype**



- Power Generation
- Economical Prospect

ITER is the core machine in 3<sup>rd</sup> phase of the fusion R&D plan, and it is an “experimental reactor of Japan” being constructed in France under international collaboration.


JT-60



**Broader Approach (BA) Activities**

June 2007 ~

[Naka, Ibaraki]



- Satellite Tokamak (JT-60 Superconducting)

[Rokkasho, Aomori]



- IFMIF
- Prototype reactor design
- Simulation research

1985~

2007~

Middle of 21<sup>st</sup> century

# QST In-Kind Procurement by Japan




## Toroidal Field (TF) Coil

TF Conductors: 25%  
TF winding, assembly: 47%  
TF Structures: 100%



## Center Solenoid (CS) Coil

CS conductors: 100%



## Diagnostics

(under design)

- Micro Fission Chamber
- Poloidal Polarimeter
- Edge Thomson Scattering
- Divertor Impurity Monitor
- IR Thermography
- Thermocouples
- Upper Port Integration
- Lower Port Integration

## Electron Cyclotron H&CD

Equatorial Launcher  
Gyrotron

## Neutral Beam H&CD

HV Bushing: 100%  
1 MV Power Supply HV part: 100%  
1 MeV Accelerator: 33%




## Detritiation System

(ADS, under design)





## Divertor

Outer Target: 100%




## Blanket Remote Handling System

(under design)



# QST Procurement Arrangement



JADA has signed 12 PAs, corresponding to about 90% in credit value out of total Japanese contribution to the ITER in-kind procurement.



## Strand

(~20km/piece)



cross section  
( $\phi 0.82\text{mm}$ )



strand wound in spools

Total Manufacturing:  
23,000 km (~100ton)

## Cable



Cable wound in a spool

Total Manufacturing:  
760m 24 units  
415m 9 units




## Conductor

- 760 m (7.3 ton) x 24 units: **completed**
- 415 m (4.0 ton) x 9 units: **completed**



Overview of conductor manufacturing factory


## Jacket for TFC (13m/piece)



welding to unit length

X-ray inspection

Jacket  
13m



760m or 415m



43.7mm




Cable pulling to jacket (<4ton)  
Compaction  
Winding for transportation



Final shape of a TF conductor

**JA has successfully completed procurement of all TF conductors.  
84% CS conductors has completed, and 69% already shipped to US.**


# TF Coil Winding (MHI)



10 DPs completed,



CP Welding



9 DPs completed,

DP Insulation



7 DPs completed,

DP Impregnation



7 DPs completed,


DP Stacking



First 7 DPs stacked for TF#1 in Dec. 2016.



# TF coil winging (MHI)



**Insulation wrapping of first 7 DPs stacked for TF#1 was completed in Jan. 2017, which is accomplishment of one of IC milestones in time.**

# TF coil winging (Toshiba)

2<sup>nd</sup> manufacturing line in Toshiba has fully commissioned for series production of TF coils.







First TF coil structure is to be completed soon by MHI and HHI.




**Outboard Sub-assembly (HHI)**  
(consisting of 4 Basic Segments)  
Waiting for final weld connection.





**Inboard Sub-assembly (MHI)**  
(consisting of 3 Basic Segments)

ITER Japan has contributed in construction of ITER NB Test facility at Padua Italy, to fulfill the requirement of ITER NB system.


The HV PS components has been almost completed by HITACHI.




**DC generators**



**HV bushing**



**1MV transmission line (TL)**




**Test power supply**





# QST Neutral Beam Test facility




Almost all components have been already installed at NBTF site at Padua Italy.




- ✓ Major requirement of ITER Gyrotron already achieved (1 MW for 1,000 s, efficiency > 50%, 5 kHz modulations, etc.).
- ✓ First Gyrotron for ITER has been delivered to QST Naka in December 2016 (on schedule). The gyrotron is to be shipped to ITER site after high power test at Naka.







JADA expects 3 PAs to be signed in next several years, followed by contract awards for manufacturing of various components.



JADA on-site activities from receipt on-site till completion of Integration tests etc. since mid. 2018 to 2032, requires support of European companies.



- Most of the on-site assembly, installation works are to be carried out by IO. The on-site integration test etc. shall be carried out under initiative of IO. **JADA supports the IO activities sending scientists and engineers for supervisory.**
- For this activities JADA expects following support from EU companies:
  - ✓ **Interpreter**, with good understanding of related technology,
  - ✓ Engineer with experience of **crane handling of heavy weight components** (for TF coil, NB HVPS),
  - ✓ **Electric/mechanical engineer** capable of assembly of HV components (for NB HVPS),
  - ✓ Mechanical engineer for **precision instruments** (for ECH gyrotron, launcher, Blanket RH, Diagnostics),
  - ✓ **Plant engineer** (for ADS).

**Current contribution of Foreign Company to the JADA in-kind components for ITER are as follows:**

- **Tungsten mono blocks for Divertor Outer Target** <sup>\*1</sup>
  - mono blocks (JFY2009, 2010, 2014) : **AT&M and TLWM (CN)**
- **Fabrication of TF Coil structure**
  - TF Coil structure Materials :  
**KIND (Germany)<sup>\*2</sup>, Industeel (France)<sup>\*2</sup>, FAV (Italy) <sup>\*3</sup>**
  - TF Coil structure (Phase III) : **HHI (Korea) <sup>\*4</sup>**
- **CS strand and cable for CS1U Module and CS2U Module**
  - (6 x 933m + 628m) : **Kiswire Advanced Technology (Korea) <sup>\*4</sup>**
- **Blanket Remote Handling System**
  - **Review and design of part of BRHS : PAR system (USA) <sup>\*4</sup>**

■ Note

\*1: contract with JADA through Japanese company, Marubeni Utility Service.

\*2: contract with JADA through Japanese company, MHI, e-Energy /HHI, Toshiba.

\*3: contract with JADA through Japanese company, e-Energy /HHI.

\*4: contract with JADA through Japanese company, e-Energy.



- The procurement of **TF Coil conductor** was completed.
- The **TF Coil conductor winding** has been completed for first 7 DPs of TF coil No.1.
- **1 MV HV power supply components** and **HV bushing** were manufactured and 80% of them have been installed at **NBTF** site at Padua, Italy.
- **170 GHz, 1 MW gyrotrons** #1 and #2 have been manufactured.
- Fabrications are in progress for **TF Coil, TF Coil structures, CS conductor**.
- Design and Qualification are on-going for **Blanket remote handling system, Launcher of EC system, Diagnostics** and **ADS**.
- **JADA is looking for good European companies which can support our on site activities.**

- Procurement of in-kind components of ITER is being processed according to the procurement procedure and regulations of JAEA.
- Contract process of JAEA is general competitive bidding for ensuring the transparency of contract .<sup>\*1, \*2</sup>
- Solicitation of comments on reference specifications (draft) is performed to finalize reference specification
- Before the Call for Tender, information for bidding is published on Official Gazette based on Governmental Procurement
- After tendering, technical review will be done for the selection of supplier.

## ■ Note

- \*1: Suppliers who join the bidding of JAEA contract need the registration process to Contract Dept. of JAEA before bidding.
- \*2: The bidding specifications shall be written in Japanese language.



## Selection of Supplier

- **Technical evaluation will be done for the selection of supplier by review of the documents.**
- **The following required items and criteria for evaluation will be specified in the reference specifications.**
  - **Record of supply for the applicable product to JAEA or other organizations;**
  - **Record of supplying similar products to JAEA or other organizations;**
  - **the tender evaluation criteria specified in the PA;**
  - **the required features of the Supplier's QA system; and**
  - **characteristics of the required manufacturing facilities.**
- **The criteria for selection will be determined according to the PA or agreement with IO. Criteria will be included in the reference specification.**

**JADA has implemented the following project management tools/methods for smooth execution of Procurement of ITER components:**

## **1. Schedule monitoring**

- Primavera (DWS, between IO and JADA) and
- Microsoft Project (monitoring of detailed resource loaded activity between JADA and Supplier)

## **2. Requirement management**

- Compliance matrix

## **3. PA follow-up meeting**

- Every 2weeks, for each PA, held with procurement Gr. (PBS) and Support Gr. (Project Management)
- Status of design/manufacturing and schedule
- Achievement of Milestones on DWS (AWP/SMP/CDWS)
- Resource availability/adequacy of each activity
- Risk management table with prevention/mitigation actions


## **4. Domestic Design review**

- Dry-run held before CDR/PDR/FDR in IO
- Review all technical/managerial materials, and confirm the design maturity

**This Project management is successful, achieving 93% of AWP SMP (100% taking into account "obsolete") and 100% of AWP CDWS in 2014.**




**Outboard Sub-assembly**  
(consisting of 4 Basic Segments  
before welding B1+B2 and B3+B4)



AP Sub-assembly

**Inboard Sub-assembly** (consisting of 3 Basic Segments)




The sub-assemblies have been welded within required tolerance.


# QST Full Tungsten Divertor Outer Vertical Target Prototype Plasma Facing Units



(1) Completion of manufacturing of full tungsten OVT prototype PFUs (Mar. 2015)



(2) Successful completion of high heat flux test (Dec. 2015)




- (1) Manufacturing of full tungsten OVT prototype PFUs has been completed.
- (2) High heat flux test of the prototype PFUs has been completed, and JADA has successfully been qualified in December 2015. ➡ See Shimizu, IVC session on Day 3



- ✓ PAs signed in Dec. 2011.
- ✓ Final Design Review for Package 1 (Vehicle and Manipulator) was closed in Jan. 2015.
- ✓ Final Design for other components in progress for FDRs to be held in 2017 and 2018.
- ✓ Manufacturing contract for Procurement Package 1 was awarded in Feb. 2015. Manufacturing design is on-going.
- ✓ Call for tender is on-going for manufacturing contract for Procurement Package 2 (rail deployment system).


**Design on-going including structural analysis.**

**Design seismic load:  
5G in peak (SL-1)**




**Test for design justification is also on-going such as irradiation test.**

**AC Servo motors confirmed to work after 8MGy irradiation (ITER requirement: 1MGy)**



R&D for Vacuum Feed-through (SIC) of Micro Fission Chamber in progress.

Preliminary Design Review of Poloidal Polarimeter was held in Nov. 2015



Radiography Test by inserting film detected welding defects.

New building for development of ITER diagnostic systems was constructed in March 2015.



Front UPP mirror module

Rear UPP mirror module

EPP mirror module

RR assembly on FW

RR assembly on divertor

In-Vessel Mirror Design